


# WOODFIELD

## SECTION SIX, PHASE TWO

### SECONDARY PLAT



I, the undersigned, a Registered Land Surveyor in the State of Indiana, hereby certify that the within plat represents a survey and subdivision of Part of the Northwest Quarter of Section 21, Township 18 North, Range 4 East in Clay Township, Hamilton County, Indiana, described as follows: Commencing at a point on the east line of said quarter section being North 00 degrees 19 minutes 15 seconds East (assumed bearing); 824.98 feet from the southeast corner thereof; thence North 89 degrees 38 minutes 38 seconds West 340.00 feet to the POINT OF BEGINNING; thence North 89 degrees 38 minutes 15 seconds West along the north line of Woodfield, Section Three, a subdivision in Hamilton County, Indiana, the plat of which is recorded in Plat Book 12, pages 33 and 34 in the Office of the Recorder of Hamilton County, Indiana, a distance of 501.00 feet; thence North 00 degrees 19 minutes 15 seconds East parallel with the east line of said quarter section 494.08 feet; thence South 89 degrees 40 minutes 45 seconds East 155.50 feet; thence North 0 degrees 19 minutes 15 seconds East parallel with the east line of said quarter section 26.67 feet; thence South 89 degrees 40 minutes 45 seconds East 205.50 feet; thence South 00 degrees 19 minutes 15 seconds West 24.42 feet to a point on the north line of Woodfield, Section Four, a Subdivision in Hamilton County, Indiana, the plat of which is recorded in Plat Book 14, page 41 in the Office of the Recorder of Hamilton County, Indiana; thence, the following 6 courses being along the boundary of Woodfield, Section Four, (1) North 89 degrees 32 minutes 43 seconds West 0.78 feet, (2) South 14 degrees 05 minutes 44 seconds West 135.06 feet, (3) South 83 degrees 08 minutes 26 seconds East 78.00 feet, (4) South 01 degrees 40 minutes 11 seconds East 218.05 feet to a point on a nontangent curve, the radius point of which lies North 02 degrees 46 minutes 48 seconds West 385.00 feet from said point; (5) thence northeasterly along said curve an arc distance of 51.57 feet to a point which lies South 10 degrees 27 minutes 18 seconds East 385.00 feet from said radius point; (6) thence South 13 degrees 53 minutes 40 seconds East 149.52 feet to the Point of Beginning, containing 4.807 acres, more or less. Subject to all legal easements and rights of way. This subdivision consists of 9 lots, numbered 136 through 144. The size of the lots and width of the street rights of way are shown in figures which denote feet and decimal parts thereof.

Witness my signature this 29th day of July, 1988.


*Frank M. Hahn*



North Line S 1/2 N.W. 1/4 Sec. 21-18-4E.

Instrument No. 8908378  
P.C. No. 1 Slide No. 17

DULY ENTERED FOR TAXATION  
Subject to final acceptance for transfer  
27 day APRIL 1989  
Polly Pearce Auditor  
Hamilton County



WOODFIELD, SECTION FOUR  
(P.B. 14, page 41)

Curve	Arc	Delta	Radius	Chord	Tangent
C-1	103.57'	12° 44' 15"	465.88'	103.36'	52.00'
C-2	109.13'	12° 44' 15"	490.98'	108.90'	54.79'
C-3	114.69'	12° 44' 15"	516.88'	114.45'	57.58'
C-4	93.57'	16° 00' 15"	335.00'	93.27'	47.09'
C-5	100.00'	15° 54' 56"	360.00'	99.68'	50.32'
C-6	158.00'	23° 30' 48"	395.90'	156.89'	80.18'
C-7	76.70'	12° 44' 15"	345.00'	76.54'	38.51'
C-8	81.26'	12° 44' 15"	370.00'	81.09'	41.30'
C-9	81.81'	12° 44' 15"	395.00'	81.65'	44.09'

Note: Property lines @ all street intersections are rounded by a radius of 20 feet; however, dimensions shown are to the P.I. of said curve.

■ - denotes conc. monument set, iron pins to be set @ lot corners after construction

WOODFIELD, SECTION THREE  
(P.B. 12, pages 33-34)

This instrument was prepared by Frank M. Hahn & Associates, Inc. 98 e. 102nd st. Indpls., IN 46280

S.E. Corner N.W. 1/4 Sec. 21, T.18 N., R.4E.  
East Line N.W. 1/4 Sec. 21-18-4E.

WOODFIELD SECTION SIX Covenants and Restrictions

The undersigned, Robert C. Langston and Sue G. Langston, owners of the real estate shown and described herein, do hereby certify that they have laid off, platted and subdivided and do hereby lay off, plat and subdivide, said real estate in accordance with the within plat. The following restrictions, limitations and covenants are hereby imposed upon and shall run with the land contained in such plat.

This subdivision shall be known and designated as WOODFIELD subdivision in Hamilton County, Indiana. All streets shown and not heretofore dedicated are hereby dedicated to the public.

Front and side yard building setback lines are hereby established as shown on this plat, between which lines and the property lines of the street, there shall be erected or maintained no building or structure.

There are strips of ground as shown on this plat and marked Drainage and Utility Easement, reserved for the use of public utilities for the installation of water and sewer mains, poles, ducts, lines and wires, subject at all times to the proper authorities and to the easement herein reserved. No permanent or other structures are to be erected or maintained upon said strips of land, but owners of lots in this subdivision shall take their titles subject to the rights of public utilities.

Areas shown on this plat and marked as Detention/Retention shall be recorded as drainage easements, reserved for the installation and maintenance of storm sewer structures and subject at all times to proper City and/or County authorities and the easement herein reserved. These areas shall be maintained free of weeds, trash, or other obstruction by the homeowner or Homeowner's Association.

All lots in this subdivision are reserved for residential use, and no building other than a one-family residence or structure or facility accessory in use thereto shall be erected thereon.

Not more than one building shall be erected or used for residential purposes on any lot in this subdivision.

The ground floor area of the main structure, exclusive of one-story open porches and garages, shall not be less than Twenty-Six Hundred (2600) square feet in the case of a one story structure, nor less than Sixteen Hundred (1600) square feet in the case of a multiple story structure, provided no structure of more than one story shall have less than an aggregate of Thirty-Two Hundred (3200) square feet of finished and livable floor area. All garages shall be attached to the residence dwelling and be a minimum of Three car size.

No trailer, tent, shack, attached shed, basement, garage, barn, or other out-building or temporary structure shall be used for temporary or permanent residence on any lot in this subdivision. An attached garage, tool shed or detached storage building erected or used as an accessory to a residence in this subdivision shall be of permanent type of construction and conform to the general architecture and appearance of such residence. No swimming pools shall be constructed in areas reserved as easements.

No fence shall be erected in this subdivision between the building lines and the property line of the streets as shown on the within plat, except with the approval of the Developer, which fences shall not exceed 42 inches in height and shall be of a decorative nature. No fences shall be constructed in areas designated for Detention / Retention.

No building structure or accessory building shall be erected closer to the side of any lot than ten (10) feet. Where buildings are erected on more than one single lot this restriction shall apply to the side lines of the extreme boundaries of the multiple lots.

No structure in this subdivision, without special approval from the Developer shall exceed two and one-half (2 1/2) stories or Twenty-five (25) feet in height measured from finished grade to the underside of the eave line, and no structure other than an open porch shall be erected between the building line as designated on the plat and the property line of the street.

No boat, trailer, or camper of any kind (including but not in limitation thereof, house trailers, camping trailers, or boat trailers), or any disabled vehicle shall be kept or parked on any lot except within a garage or other approved structure.

No building shall be erected, placed or altered on any building plot in this subdivision until the building plans, specifications, and plot plan showing the location of such building have been approved as to the conformity and harmony of external design with existing structures herein and as to the building with respect to topography and finished ground elevation, by the Developer, owner of the herein described real estate, or by their duly authorized representatives.

If the Developer fails to act upon any plans submitted to it for its approval within a period of fifteen (15) days from the submission date of the same, the owner may proceed then with the building according to the plans as approved. Neither Developer nor the designated representatives shall be entitled to any compensation for services performed pursuant to this covenant.

In the event storm water drainage from any lot flows across another lot, provision shall be made to permit such drainage to continue, without restriction or reduction, across the downstream lot and into the natural drainage channel or course, even though no specific drainage easement for such flow of water is provided on said plat.

Outlets for sump pump water will be provided for each lot in this subdivision by the developer or home builder at the time of lot development. If during excavation of the foundation for crawl space or basement, ground water is encountered, or if the house location is in an area of high water table (as per Hamilton County Surveyor or City of Carmel), an outlet will be provided directly to a storm sewer or approved open ditch with plastic pipe. The route of outlet will be via platted easements and approved by proper agencies. Where a storm sewer exists on or directly adjacent to a subject lot, all sump pumps shall tie directly to storm sewer via underground pipe. Lots not located in an area of high water table may outlet sump pump water in the rear yard, no closer than 25 feet from established lot lines or platted easements.

Construction of any sump pump outlet will commence only when appropriate construction plans have been submitted and approved by the proper agencies and applicable permits issued from the local building authority. Where construction will be in established drainage and/or utility easements, approval must be obtained from City of Carmel or Hamilton County Surveyor. The maintenance of drainage pipes and facilities for discharging sump pumps shall be the responsibility of the individual homeowner and/or a homeowner's association.

Geo-thermal heat pumps shall be of the closed loop type only.

No noxious, unlawful, or other offensive activity shall be carried out on any lot in this subdivision, nor shall anything be done thereon which may be or may become an annoyance or nuisance to the neighborhood.

Lots numbered 92 through 102 inclusive shall have a minimum aggregate livable floor area of 4000 square feet.

No animals, livestock, or poultry of any description shall be raised, bred, or kept on any lot, except that dogs, cats, or other household pets may be kept, provided that they are not kept, bred, or maintained for commercial purposes.

All <sup>Developers</sup> or Builders will be required to install, or have installed, at least one gas or electric "dusk to dawn" yard light in the front yard. All garages opening to the street shall automatic door controls. All yards shall be sodded.

No lot in this subdivision shall be used or maintained as a dumping ground for rubbish, trash, garbage, or other waste, and shall not be kept, except in sanitary containers. Trash shall not be burned, except in suitable incinerators.

Lot owners, upon taking title, agree to waive all rights to oppose future zoning changes and special permits necessary to complete the Master Plans of WOODFIELD.

It shall be the duty of the owner of each lot in the subdivision to keep the grass on the lot properly cut and to keep the lot free from weeds and trash and otherwise neat and attractive in appearance. Should any owner fail to do so then the Developer may take such action as it deems appropriate in order to make the lot neat and attractive and the owner shall upon demand reimburse Developer for the expense incurred in so doing.

The foregoing covenants (or restrictions) are to run with the land and shall be binding on all parties and all persons claiming under them for a period of Twenty-five (25) years from the date of this plat, at which time said covenants, (or restrictions), shall be automatically extended for successive periods of Ten (10) years unless changed by vote of a majority of the then owners of the buildings covered by these covenants, or restrictions, in whole or in part. Invalidity of any one of the foregoing covenants or restrictions, by judgement or court order shall in no way affect any of the other covenants or restrictions, which shall remain in full force and effect.

The right to enforce these provisions by injunction, together with the right to cause the removal by due process of law, of any structure or part thereof erected, or maintained in violation hereof, is hereby dedicated to the public, and reserved to the several owners of the several lots in this subdivision and to their heirs and assigns.

No owner of any lot shown herein shall have the right to remonstrate against annexation of that lot to the City of Carmel.

OWNER and SUBDIVIDER  
Robert C. Langston and Sue G. Langston

by RC Langston by Sue G. Langston  
Robert C. Langston Sue G. Langston

State of Indiana ) ss:  
County of Hamilton )

Before me, the undersigned, a Notary Public, in and for said County and State, personally appeared Robert C. Langston and Sue G. Langston who acknowledged the execution of the foregoing instrument as their voluntary act and deed, for the purposes therein expressed.

Witness my hand and Notarial Seal this 21<sup>st</sup> day of March, 1986.

Notary Public Barbara A. Skellett

My Commission Expires 9-22-89 County of Residence Hamilton

UNDER AUTHORITY PROVIDED BY CHAPTER 178, ACTS OF 1981, PUBLIC LAW 309 SECTION 23, ENACTED BY THE GENERAL ASSEMBLY OF THE STATE OF INDIANA, AND ALL ACTS AMENDATORY THERETO, AND AN ORDINANCE ADOPTED BY THE COMMON COUNCIL OF THE CITY OF CARMEL, INDIANA, THIS PLAT WAS GIVEN APPROVAL BY THE CITY OF CARMEL AS FOLLOWS:

Adopted by the Carmel City Plan Commission at a meeting held Mar 10<sup>th</sup>, 1988.

CARMEL CITY PLAN COMMISSION

Wesley G. Bucher  
Director of Comm. Dev.  
WESLEY G. BUCHER

BOARD OF PUBLIC WORKS AND SAFETY CERTIFICATE

THIS PLAT WAS GIVEN APPROVAL BY THE BOARD OF PUBLIC WORKS AND SAFETY OF THE CITY OF CARMEL, INDIANA AT A MEETING HELD ON THE 17 DAY OF April, 1988.

Dorothy J. Hancock William D. McFadden  
Dorothy J. Hancock Mayor WILLIAM D. McFADDEN

attest:  
Susan W. Jones  
SUSAN W. JONES